

Grid connection requirements of Renewable Energy

Presented by: Riaan Smit
Chief Engineer:
Network Planning

2010-09-28

Content

- Summary of interest in renewable energy developments to date
- Renewable Energy Development Areas
- Embedded Generation (EG) Applications
- Interconnection of Embedded Generation
- Joint Transmission & Distribution Grid Planning
- Western Cape GTZ-DigSilent-Eskom grid integration study
- Conclusion
- Q&A



2010/09/28

Renewable Energy “Potential” Summary (MW)



- | Development interest in MW: | WR | SR | NWR | Total |
|---|------------|-----------|--------------|--------------|
| • Wind Applications (Letter, Rev 1&2) | 6 350 | 5 212 | 1 682 | 13 252 |
| • Other RE sources | <u>795</u> | <u>20</u> | <u>1 082</u> | <u>1 902</u> |
| • Requests for RE Grid Connection | 7 145 | 5 232 | 2 764 | 15 154 |
| • Number of “application” projects | <u>85</u> | <u>45</u> | <u>24</u> | <u>156</u> |
| • Max potential listed for these sites | 12 172 | 5 519 | 5 063 | 22 772 |
| • Alternatives, Duplicate sites, too close to coast, “long term dreams”,..... | | | | |
| • New applications will assist with data cleanup - latest requirements | | | | |
| • Formal process Applications expected ?? | | | | |
| • Expected approval levels by 2013 (IRP1) | | | | 1 025 |
- Actual RE potential Precisely unknown
 - Uncertainty high Await IRP 2 by Nov 2010 / REFIT programme
 - Excellent cooperation by potential developers – to share data
 - Database with RE Projects shared with Eskom Network Planners only




2010/09/28

3

Renewable Energy Development Areas (REDA) – Indicative “applications”



- MTS substation areas / Technical Areas
- Numerous extra ~500 MVA substations required – long term
- Additional transformer capacity required
- Allow 3+ year lead time – EIA, technical & resource, etc.
- Funding for shared networks need NERSA approval



2010/09/28


Embedded Generation (EG) Applications



- Use Eskom EG Application form Revision 02, Dated 30 June 2010
- Forward request for Indicative Costs on Company Letterhead and Rev 2 to Customer Services (see contacts below)
- All letters, Rev 1 and Rev 2 considered in scenarios
- Formal national process not initiated as yet – all are waiting
- Company & Technical data

are.vanzyl@eskom.co.za	Western Region
billy.madike@eskom.co.za	Central Region
dirk.opperman@eskom.co.za	North West Region
eddie.leach@eskom.co.za	Southern Region
wolfgang.bohmer@eskom.co.za	Northern Region
ravi.moonsamy@eskom.co.za	Eastern Region

2010/09/28



Renewable Energy applications



- Applications to be processed once REFIT programme requirements fully available
- Indicative costs to support developers
- A quotation requires detail work for project submissions – Application Form Rev 2 Part 2 to be updated with all required technical data
- Selected projects to continue once commitment fee is paid to Budget Quote stage
- Project execution will follow once PPA allocated / financial close
- Will require a Connection and Use of System Agreement to be signed
- Any programme must cater realistically for project lead times and risks, including quotation phase, EIA, construction....



2010/09/28

6

Interconnection of Embedded Generation



- SA Grid Code (Transmission) and Distribution Grid Codes from NERSA
- DST 34-1765 Distribution standard serves to fulfil Eskom Distribution's obligation under Section 8.2 (4) of the South African Distribution Code: Network Code:
 - "The Distributor shall develop the protection requirement guide for connecting Embedded Generators to the Distribution System to ensure safe and reliable operation of the Distribution System".
- This standard does not apply to generator interconnections at Low Voltage, or generators of capacity less than 100kW. NRS097 will cater for it.
- The present revision of this standard does not cater for specific requirements with regard to the interconnection of wind farms
 - Additional Wind Grid Code requirements under development
- Will require developer/IPP cooperation with proper technical data
 - E.g. wind turbine models



2010/09/28

7

Joint Transmission & Distribution Grid Planning



- First real wind energy course in South Africa – March 2009
 - Arranged by DEADP, Western Province and Eskom with GTZ & DigSilent
 - Involved various role players and developers in industry
- GTZ-DigSilent-Eskom Western Province grid capacity study – March – Nov 2009
- GTZ-DigSilent-Eskom grid capacity credit study – March – Oct 2010
- Transmission and Distribution in-house network capacity, and fault studies in progress
 - Will be used in feedback to developers to assist with applications
 - Transmission & Distribution workshop held Sep 2010
- Planning procedures being developed and tested
- Developers treated as if only developer, until optimisation for projects accepted for REFIT programme
- DigSilent wind turbine modelling course to Eskom Network Planners – Oct 2010 – to support proper analysis and consistent approach
- The above deals only with Eskom, Municipal needs to be considered



2010/09/28

8

Stage 1: 150MW – Impact on Thermal Limits




• **<=127% overload**

- General mitigation options > thermal limits
- Build new 143 km line to Boskloop
- Limit wind farm output to 120MW
- Limit output in case of actual line failure
- Consider dynamic line rating systems
- Or just limit size of Wind Energy Facility


150 MW Wind Park



2010/09/28




Violation of Thermal Limits – Cap Wind Farm Output



2010/09/28


Voltage Variations – cos phi constant (=1)



2010/09/28




Voltage Variations – cos phi(P)-characteristic



2010/09/28



Specialist studies – e.g. Impact on Short Circuit Currents




- DFIG:
 - Considerable contribution to peak short circuit current.
 - Contribution to thermal short circuit ratings: approx 1 p.u. shc-current
- WTG with fully rated converter:
 - Contribution to initial short circuit current: approx. 1 p.u. shc-current
 - Contribution to thermal short circuit ratings: approx 1 p.u. shc-current
- 150MW wind farm at Laingsburg:
 - Contribution to initial shc-current (Ikss): approx 2 kA (at 132kV)
 - Contribution to peak shc-current (ip): 4,4 kA
 - Contribution to transient shc-current (Iks): 0,67 kA
- Contribution to fault levels not critical in this particular example because of low fault level at wind farm connection point.



2010/09/28

SILENT
DIG


Stage 2 – 750MW of Wind Gen in Karoo Represent a group of green field projects - example



2010/09/28

SILENT
DIG

Stage 2 – 750MW wind in Karoo - Voltages




2010/09/28

Stage 2 – 750MW – Summary of Results

- No thermal overloads under n-1 conditions
- Voltage variations very small, even in constant power factor operation.
- Operation with constant Q (var-control) is appropriate.
- (Slow) voltage control is possible and should be considered.
- **4x100Mvar shunt reactors required at Nuweveld substation (or equivalent var-absorption of the wind farms) because of proximity to Komsberg series compensation.**
- **Series compensation at Komsberg should be resized for considering new line configuration.**
- **With adjusted series compensation, shunt reactors at Nuweveld might not be required.**
- No power quality issues because of the large number of turbines and high fault level at the grid connection point

2010/09/28




Conclusion

Extract Energy Expand Vision

- Various exciting disciplines
- Skills development good progress
- Methods and techniques being improved
- Eskom application form available
- Embedded Generation standard
- REDA being studied – to motivate long term grid solutions
- Await REFIT Rules & Criteria & IRP to determine grid requirements
- Need long term allocations and approvals to ensure 3-7 year large infrastructure lead times can be met
- Let us make RE work

2010/09/28



Thank you

Riaan Smit
riaan.smit@eskom.co.za

Contributions by:
Nish Rathanlall
Shirley Salvoldi